Generation-X

Reliability/Safety



Dick Bolt July 27, 2000



Reliability Summary

- ◆ Constellation Reliability Will be Low for 5 Year Mission if 4 are Required
- **♦ New Technology & Deployed Items Present Mission Success Problems**
 - Assemble & Test at LEO of as Many Subsystems as Possible
- ◆ Design for Least Deployments at L2
 - Body Mounted Solar Cells
 - Design for Petals &/or Antennas deployed at LEO
- **♦ LEO Assembly Reliability Benefit**
 - Based on Ability to Replace or Repair at LEO
 - Robotic Deployment I tems are not likely to be tested until on station



Constellation Mission Success

♦ Based on a 5 Yr Mission


- One S/C will have only 52% Reliability based on an estimated failure rate of 15 failures X 10-6 hrs.
- Mission Success Criteria of 1 Out-of 4 operating needed to approach 70% Constellation Reliability!
- Attached is curve for 3 out-of 4 S/C

Based on a 3 Yr Mission

- One S/C will have only 67 % Reliability based on an estimated failure rate of 15 failures X 10-6 hrs.
- Mission Success Criteria of 2 Out-of 4 Operating needed to approach 70% Constellation Reliability.




5 Year Mission-Mission Success 3 out-of 4 S/C





Gen-X Reliability Block Diagram





Reliability Assumptions & Mission Success

Assumptions

- Each S/C of the 4 units will have a Total Failure Rate in the 10-30 Failures per Million Hrs.
- Five (5) Yr Mission
 - Mission Success at 1 out-of 4 Operating > 99-70%
 - Mission Success at 2 Out-of 4 Operating > 90-30%
 - 3 Out-of 4 Operating > 78-25%
 - 4 Out-of 4 Operating > 20-0%
- Three (3) Yr Mission
 - Mission Success at 1 Out-of 4 Operating > 99-92%
 - Mission Success at 2 Out-of 4 Operating > 97-60%
 - 3 Out-of 4 Operating > 78-25%
 - 4 Out-of 4 Operating > 35-5%



Safety

- ◆ Standard EWR 127-1 Safety Requirements for WTR (Vandenberg) & ETR (KSC/Patrick AFB)
- KSC Bookmarked on Task Sheet
 - Hydrazine
 - High Pressure Batteries





